

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21495-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 25-31S-9W
2310 feet from S Section Line, 660 feet from W Section Line
Lease Name: ANTRIM Well #: 3
County: HARPER Total Vertical Depth: 4507 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 912 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	4270		
SURF	8.625	235		185sx
PROD	5.5	4506	2452	150sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2011 8:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE Phone: _____

Proposed Plugging Method: CIBP 4050 2 SKS CMT, 35 SKS 1400', 35 SKS 950', CIRC CMT 285-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2011 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4050'. AND CAPPED WITH 2SKS OF CMT. THE CASING WAS RECOVERED FROM 2452' AND PULLED TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 299', WHERE CMT WAS CIRC'D TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4082	4093	CSG	

Remarks: ALLIED CMTG 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
APR 11 2011

KCC WICHITA