

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20715-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 26-13S-16W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: J M DORTLAND Well #: 1
County: ELLIS Total Vertical Depth: 3510 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227	0	150 SX.
T1	2.375	3425		
PROD	4.5	3509	0	75 SX.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2011 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING CO., INC. Phone: (620) 546-3388

Proposed 04-05-2011 - Ordered 150 sxs 60/40 pozmix - 4% gel - 150 sxs common cement - 200# hulls.
Plugging 04-06-2011 - Ordered 200 sxs 60/40 pozmix - 4% gel - 3% c.c. - 100# hulls.
Method: Junk in the hole - rods at 800' - top of tubing approximately 1450'.
Milled on well for 3 days. Started milling at 650' - got to approximately 1450' - could not get any further.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2011 8:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

04/05/2011 - Log Tech perfed two shot hole at 1451' - 1040'.
Express Well Service RIH with one inch tubing to 1475'.
Basic Cementing rigged to tubing and pumped 50 sxs cement.
Pulled tubing to 745'. Basic rigged to tubing and pumped 86 sxs cement - lost circulation.
Pulled tubing to 340' - rigged to tubing and pumped 14 sxs 60/40 pozmix with 30 sxs common - no circulation.
Pulled tubing let - set two hours.
Pumped 120 sxs common with 200# hulls.
No returns - shut down for the night.
04/06/2011 - Started at 7:30am. Pumped 50 sxs 60/40 pozmix - 3% cc with 100# hulls to fill up 4 1/2" casing - hole standing full.
8 5/8" casing was full of cement.


Perfs:

Top	Bot	Thru	Comments
3444	3446		
3218	3218		SPF
3214	3215		LKC

Remarks: BASIC CEMENTING COMPANY-TICKET #03877A.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

RECEIVED Form CP-2/3
APR 08 2011

APR 06 2011

KCC WICHITA