

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20447-00-00
Spot: SENE Sec/Twnshp/Rge: 9-13S-21W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: KELLER Well #: 1
County: TREGO Total Vertical Depth: 3893 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256	0	165 SX
PROD	4.5	3888	0	225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2011 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: ALAN Company: TENGASCO, INC. Phone: (865) 675-1554

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 10 sxs gel - 400# hulls.
PBTD at 3820'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2011 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3700' - pumped 10 sxs gel - followed with 40 sxs cement with 300# hulls.
Pulled tubing to 1600' - pumped 120 sxs cement - good circulation.
Pulled tubing out - tied onto backside - pumped 10 sxs cement - full - shut in.
Pumped 15 sxs down casing - full.

Perfs:

Top	Bot	Thru	Comments
3672	3676		
3664	3668		
3624	3631		
3580	3594		
3539	3543		
3526	3530		
3520	3524		
3485	3491		
3470	3476		

RECEIVED
MAR 21 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #36437.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

Form CP-2/3

MAR 16 2011