

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21647-00-01
Spot: E2NESE Sec/Twnshp/Rge: 12-11S-19W
1980 feet from S Section Line, 330 feet from E Section Line
Lease Name: GLADYS Well #: 3
County: ELLIS Total Vertical Depth: 3575 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	164	0	135 SX
PROD	4.5	3479	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: Ordered 570 sxs 60/40 pozmix - 4% gel - 500# hulls.
Log Tech perfed at 1675' - 1328' - 650' - 150'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2011 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Drilled to 2050' with bit and power swivel on 03/29/2011.
Got to 1728' on 03/30/2011 - washed down to 1824'.
Could not get perforating gun past 1680' in tubing due to paraffin in tubing.
Shot first hole at 1675' - tubing at 1821'
Quality rigged to tubing and pumped 25 sxs cement.
Pulled tubing to 1328'. Log Tech perfed two hole shot.
Quality rigged to tubing and pumped 45 sxs cement
Pulled tubing to 650'. Log Tech perfed two hole shot.
Quality rigged to tubing and mixed and pumped 150 sxs cement with 200# hulls.
Pulled tubing to 325'. Quality rigged to tubing and mixed and pumped 230 sxs cement with 300# hulls mixed in - no circulation.
Pulled tubing. Perfed at 150'.
Rigged onto 4 1/2" with a swedge and pumped 50 sxs cement - well went on vacuum.
Left set overnight.
03/31/2011 - circulated 4 1/2" casing up 8 5/8" casing with 70 sxs cement.
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3380	3415		
3295	3325		


RECEIVED
APR 04 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5136.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

MAR 31 2011