

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22493-00-01  
Spot: NESENW Sec/Twnshp/Rge: 16-11S-18W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: WASINGER OWWO Well #: 1  
County: ELLIS Total Vertical Depth: 4030 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1185	0	560 SX
PROD	5.5	4030	0	240 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2011 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 672-1969

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Log Tech perfed at 1850' - 1200' - 625'.  
Top perf 3304'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2011 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality sanded off bottom to 3210' and topped with 5 sxs cement.  
RIH with tubing to 1850'.  
Quality rigged to tubing and mixed and pumped 100 sxs cement with 200# hulls mixed in.  
Pulled tubing to 1200'. Quality rigged to tubing and mixed and pumped 100 sxs cement with 100# hulls mixed in to circulate cement to surface.  
Pulled tubing and topped off 5 1/2" casing with 20 sxs cement - hole standing full.  
Ran 100' of 1" tubing down backside of 8 5/8" casing and pumped 75 sxs to circulate cement to surface.


Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5173.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

APR 08 2011 <sup>pm</sup> CP-2/3

KCC WICHITA

APR 04 2011