

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20579-00-01
Spot: NESENE Sec/Twnshp/Rge: 9-13S-21W
3883 feet from S Section Line, 402 feet from E Section Line
Lease Name: KELLER A Well #: 7
County: TREGO Total Vertical Depth: 1580 feet

Operator License No.: 32278

Op Name: TENGASCO, INC.

Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | | 1140 | | |
| SURF | 8.625 | 280 | 0 | 170 SX |
| PROD | 4.5 | 1580 | 0 | 500 SX |

Well Type: SWD

UIC Docket No: D19693.0

Date/Time to Plug: 03/15/2011 1:30 PM

Plug Co. License No.: 32332

Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE

Proposal Rcvd. from: ALAN

Company: TENGASCO, INC.

Phone: (865) 675-1554

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 400# hulls.
CIBP at 1140' - cement up to 970' from squeeze job.
Casing leak from 731' to 1043'.

Plugging Proposal Received By: MARVIN MILLS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/15/2011 4:00 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 930' - pumped 75 sxs cement with 500# hulls - good circulation of cement.
Pulled tubing out - tied onto casing - squeezed with 5 sxs cement.
S.I.P. 400#.
Tied onto backside - pumped 15 sxs cement.
S.I.P. 300#.

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1300 | 1400 | | |

Remarks: ALLIED CEMENTING COMPANY-TICKET #36438.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

cc to MIC 3/22/11 CM
Form CP-2/3

MAR 16 2011