

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20646-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 14-26S-14W  
913 feet from S Section Line, 920 feet from W Section Line  
Lease Name: FINCHAM Well #: 1  
County: PRATT Total Vertical Depth: 4457 feet

Operator License No.: 31514  
Op Name: THOROUGHbred ASSOCIATES L.L.C.  
Address: 8100 E 22ND ST STE 600  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	373		WITH 300 SX CMT
DVT		3000		
PROD	4.5	4429	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/28/2011 9:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING, INC. Phone: (620) 786-4258

Proposed Plugging Method: RUN TBG TO 2790' & SPOT 50 SX COMMON CMT. PULL RECOVERABLE 4 1/2" CASING. RUN TBG BACK IN. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/29/2011 10:20 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

**\*\*TOP OF TBG FISH @ 2902\*\*** COULDN'T WORK TBG PAST 805'. APPEARED THAT TBG WAS GOING OUTSIDE OF CASING AT 740'. PULLED TBG TO 796'. PUMPED 10 SX GEL & 400 SX CMT. CIRCULATED CMT UP 8 5/8" & 4 1/2" ANNULUS. HAD CIRCULATION BUT NO CMT UP 4 1/2" 3/29/11: TAGGED CMT AT 277' WITH TBG. CIRCULATED 4 1/2" FULL OF CMT WITH 50 SX CMT. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 200 PSIG WITH 70 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4376	4377		
4274	4280		
2842	2850		

RECEIVED  
APR 12 2011  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: TBG

District: 01

Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED

APR - 5 2011

KCC DODGE CITY

Form CP-28