

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24306-00-00  
Spot: SENENE Sec/Twnshp/Rge: 18-20S-15W  
4290 feet from S Section Line, 330 feet from E Section Line  
Lease Name: DECKERT C Well #: 1-18  
County: BARTON Total Vertical Depth: 3920 feet

Operator License No.: 33699  
Op Name: T-N-T ENGINEERING, INC.  
Address: 9250 E COSTILLA AVE #510  
GREENWOOD VLG, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		6/10/88, THEN DRILLED OUT 5/5/89
SURF	8.625	1105	0	425 SX
PROD	5.5	3917	2030	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/23/2011 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/23/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.  
Cut casing at 2030'.  
Pulled casing to 1600 - tied onto casing and pumped 125 sxs cement with 300# hulls.  
Pulled casing to 1075' - pumped 40 sxs cement with 100# hulls.  
Pulled casing to 650' - pumped 60 sxs cement with 100# hulls.  
Pulled casing to 150' - circulated cement to surface with 75 sxs cement.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3802	3804		
3794	3796		
3788	3790		SQUEEZED
3782	3784		

RECEIVED  
APR 04 2011  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

MAR 29 2011