

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-20,976-00-00

LEASE NAME Kuhn Trust

WELL NUMBER 2

SPOT LOCATION C-NW-NE

SEC. 23 TWP. 13 RGE. 21 (X) or (W)

COUNTY Trego

Date Well Completed 5-17-82

Plugging Commenced 11-4-89

Plugging Completed 11-4-89

LEASE OPERATOR AFG Energy, Inc.  
ADDRESS P.O. Box 605, Russell, KS 67665

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Marmaton Depth to top 3880' bottom 3895' T.D. 3911'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Marmaton</u>	<u>Oil</u>	<u>3882</u>	<u>3888</u>	<u>8 5/8</u>	<u>297</u>	
				<u>4 1/2</u>	<u>3943</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped down 8 5/8" w/108 sxs. 65/35 Poz. 8% gel & 1 sx. hulls - 100# and shut down. Hooked to 4 1/2", pumped 25 sx. 65/35 Poz. 8% gel, then 400# hulls in next few sxs. Finished with total down casing of 188 sx, 65/35 Poz 8% gel. Hooked back to 8 5/8" and pumped 2 sx. 65/35 Poz, 8% gel and pressured to 300#. 150# standing pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing, Inc. License No. \_\_\_\_\_  
Address Russell, Kansas 67665

RECEIVED  
STATE CORPORATION COMMISSION


STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss. NOV 21 1989  
11-21-89

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. Help me God.

(Signature) Kerry W. Presher  
(Address) P.O. Box 605 Russell, Kan.

SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of Nov., 1989

Pamela R. Steckel  
Notary Public



My Commission expires: 11-19-92

15-195-20976-00-20

SIDE TWO (Page Two)

ACO-1 WELL HISTORY

OPERATOR Frontier Oil Company LEASE NAME #2 Kuhn Trust \* SEC. 23 TWP. 13S RGE. 21W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #5 60-30. Rec. 320' M. Mis-run	3844	3885		
DST #6 60-30-60-30. Rec. 380' forthy OCM. IF 83-166 FF 166-228 ISI 1155 SIP 1135	3798	3885		
DST #7 Mis-run	3885	3924		
DST #8 60-30. Rec. 10' M. IF 10-10 ISI 15.	3885	3924		
DST #9 60-30-60-20. Rec. 230' W, 10' M. IF 41-73 FF 83-135 ISI 981 FSI 951	3918	3944		

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1982  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1982  
CONSERVATION DIVISION  
Wichita, Kansas