

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21, 191-00-00

LEASE NAME Arnold #2

WELL NUMBER _____

SPOT LOCATION NE NE NW

SEC. 23 TWP. 13S RGE. 21W (E) or (W)

COUNTY Trego

Date Well Completed _____

Plugging Commenced 11/29/84

Plugging Completed 12/4/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Southern States Oil Co.

ADDRESS Box 1365, Great Bend, Ks. 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	315'	none
				5 1/2"	3914'	1356'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set.
Plugged bottom with 5 sacks cement, sand to 3800' & 5 sacks cement. Shot pipe at 3024', 2828', 2438', 2231', 2026', 1902', 1780', 1508', & 1356'. Pulled 33 joints of pipe.
Plugged well with 50 cement, 2 hull, 12 gel, 1 hull, 100 sacks cement, 2 hull, 13 gel, 1 hull, 8 5/8 plug & 50 sacks 50/50 poz 8% gel.
Plugging complete
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

DEC 19 1984
CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 84



Irene Hoover
Notary Public

My Commission expires: _____