

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-21,703-00-00

LEASE NAME Kroeger

WELL NUMBER 23-9D

SPOT LOCATION 1400 ft north

SEC. 23 TWP. 13 330 ft west  
RGE. 21 XXX (W)

COUNTY Trego

Date Well Completed 11/12/85  
(attempted)

Plugging Commenced 2/10/86

Plugging Completed 2/10/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Held By Production, Inc/SETCO

ADDRESS 1625 Broadway, Suite 2625, Denver, CO 80202

PHONE # (303) 534-4445 OPERATORS LICENSE NO. 8362/4000

Character of Well Attempted completion- D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Marmaton Depth to top 3863 bottom 3900 T.D. 4050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Water w/ tr.oil	3863	3900	4 1/2	4049	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 6 sx 60/40 pozzmix w/ 6% gel, 3% CaCl and cottonseed hulls down backside to bring cement to surface in annulus. Shut in bradenhead w/ 600 psi. Pumped down 4 1/2 csg 50 sx 60/40 pozzmix, as above, then pumped 12 sx gel mud w/ cottonseed hulls. Dropped wiper plug, then pumped 94 sx 60/40 pozzmix w/ additives, followed by 1/2 bbl water, SIP-250 psi. Bottom cement plug from TD to 3200. Top plug from surface to 1500.

(If additional description is necessary, use BACK of this form.)

Name of Plugging-Contractor Halliburton License No. 5287  
Address 1100 East 8th, Hays, KS 67601

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

Marc T. Eckels (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Marc T. Eckels 5/22/86

(Address) 1625 Broadway, Suite 2625, Denver, CO 80202

SUBSCRIBED AND SWORN to before me this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

RECEIVED  
AUG 1 5 1986  
08-15-86

Notary Public

My Commission expires: \_\_\_\_\_

Form CP-4  
Revised 01-84