

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,741-00-00

LEASE NAME Sauer

WELL NUMBER 2

SPOT LOCATION C E/2 NW NE

SEC. 28 TWP. 13 RGE. 21 (E or W)

COUNTY Trego

Date Well Completed 8-7-85

Plugging Commenced 8-7-85

Plugging Completed 8-7-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TJD Oil Co.

ADDRESS P. O. Box 271, Hays, KS 67601

PHONE 913, 625-8384 OPERATORS LICENSE NO. 9756

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dale Balthazor

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4025'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	221'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

- 1st plug was set at 1680' w/25 sks. cement
 - 2nd plug was set at 870' w/100 sks. cement
 - 3rd plug was set at 240' w/40 sks. cement
 - 4th plug was set at 40' w/10 sks. cement
- (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dreiling Oil, Inc. License No. 730
Address Box 1000, Victoria, KS 67671

STATE OF KANSAS COUNTY OF ELLIS, ss.

I, Todd Dreiling (~~employee~~ of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

STATE CORPORATION COMMISSION
(Signature) Todd J. Dreiling
Box 127
(Address) Hays, KS 67601

SEP 9 1985
09-09-85
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 6th day of Sept., 19 85

My Commission expires: 8-30-86

Patty Dreiling
Notary Public
PATTY DREILING
Ellis County, Kansas
My Appt. Exp. _____

GEOLOGICAL REPORT

15-195-21741-00-00

DRILLING TIME

SAMPLE LO

COMPANY T. J. D. OIL COMPANY
 LEASE No. 2 SAUER
 LOCATION C E/2 NW NE
 SECTION 28 TOWNSHIP 13 S RANGE 21 W
 COUNTY Trego STATE Kansas
 FIELD Riga So.

ELEVATIONS
 K.B. 2268
 Q.F. 2265
 G.L. 2263
 MEASUREMENT FROM
KB

CONTRACTOR Dreiling Oil, Inc. Rig 1
 COMM: 8-1-85 COMP: 8-7-85
 ROTARY TOTAL DEPTH 4025-1767
 LOG TOTAL DEPTH 4024-1766
 SAMPLES SAVED FROM 3300 TO 4025
 DRILLING TIME FROM 3300 TO 4025
 SUPERVISION FROM 3500 TO 4025
 MUD TYPE Starch PROD DBA
 WELL SITE GEOLOGIST _____

CASING RECORD
222 ft 85/8"

ELECTRICAL SURVEYS
RA Gaurd Caliper
(Mercury)

DRILL STEM TESTS
1- Lans I-Pawnee
Formation Testing S

FORMATION TOPS AND STRUCTURAL POSITION

FORMATION.	SAMPLE	DATUM	E. LOG	DATUM	A	B	C	D
Anhydrite	1648	+ 620	1652	+ 616	+ 617			
Topeka ls	3351	+1083	3350	- 1082	- 1073			
Heebner Sh.	3585	- 1317	3583	- 1315	- 1304			
Toronto	3601	- 1333	3602	- 1334	- 1324			
Lansing- Kansas City	3619	- 1351	3618	- 1350	- 1342			
Base Kansas City	3871	- 1613	3869	- 1611	- 1587			
Marmaton (Pawnee)	3948	- 1680	3948	- 1680	- 1674			
Conglomerate					- 1721			
Arbuckle					- 1772			

RECEIVED
 SEP 9
 STATE CORPORATION COMMISSION
 Conservation Division
 Wichita, Kansas

REFERENCE WELLS FOR STRUCTURAL POSITION

No. 1 Sauer	SW NW NE	Sec. 28 - T13S - R21S

Lawrence F. Gray

Petroleum Geologist

1728 NOTTINGHAM CT. WICHITA, KANSAS, 67203

PHONE AC 316 838-7295