

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-20,708-00-02

LEASE NAME LOFLIN

WELL NUMBER 1

SPOT LOCATION C S/2 NE

SEC. 27 TWP. 13 RGE. 21 ~~XXXX~~ (W)

COUNTY Trego

Date Well Completed 1/23/81

Plugging Commenced 6/26/84

Plugging Completed 6/28/84

LEASE OPERATOR Petroventures, Inc.

ADDRESS 165 So. Union Blvd., Suite 670, Lakewood, CO 80228

PHONE # (303) 986-9560 OPERATORS LICENSE NO. 6041

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, KS - Carl Goodrow

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Marmaton Depth to top 4026 bottom 4041 T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil & Water	4026	4041	8-5/8"	244'	-0-
				4-1/2"	4095'	2367.76'

RECEIVED  
STATE CORPORATION COMMISSION

07-30-84

JUL 30 1984

Describe in detail the manner in which the well was plugged, indicating where the mud was introduced and the method or methods used in introducing it into the hole. If other plugs were used state, the character of same and depth placed, from feet to feet each set. Pull rods, pump, tubing; spot 5 sx cement, 5 sx sand, 5 sx cement in casing. Cut and pull casing; pump 3 sx hulls, 35 sx gel, 100 sx cement, 5 sx gel, 8-5/8" plug, 70 sx cement. All cement is 50/50 P07, 6% gel, 3% CaCl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service License No. 960

Address P. O. Box 458, Ness City, KS 67560

STATE OF Colorado COUNTY OF Jefferson, ss.

William L. Warburton (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W.L. Warburton

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 27th day of August 1984

George M. Haddock  
Notary Public

My Commission expires: 12-20-87