


STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 800 Bittling Building  
 Wichita, Kansas

OR  
**FORMATION PLUGGING RECORD** Strike out upper line when reporting plugging off formations.



Trego County. Sec. 19 Twp. 13 Rge. (E) 21 (W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW  
 Lease Owner Earl F. Wakefield & Doley Oil Co.  
 Lease Name Petty Well No. 1  
 Office Address 307 Union Natl. Bank Bldg., Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed May 29 19 52  
 Application for plugging filed May 29 19 52  
 Application for plugging approved May 29 19 52  
 Plugging commenced May 29 19 52  
 Plugging completed May 29 19 52  
 Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4050 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled Out
				<u>8 5/8</u>	<u>97.51</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.  
Filled with Heavy Mud from 4050 feet to 150 feet, Bridged with Halliburton Plug & 1/2 Sack Hulls to 100 feet, Heavy Mud from 100 feet to 40 feet, Bridged with Halliburton Plug & 1/2 Sack Hulls, cemented to Bottom of cellar with 10 Sacks Cement.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUN 10 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Correspondence regarding this well should be addressed to Earl F. Wakefield  
 Address 307 Union Natl. Bank Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Earl F. Wakefield (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield  
307 Union Natl. Bank Bldg.  
Wichita, Kansas (Address)



E. J. Gaffney  
 Notary Public.

PLUGGING  
 FILE SEC 19T 13R 21W  
 BOOK PAGE 19 LINE 51

Petty #1  
 Owner: Earl F. Wakefield &  
 Doley Oil Co.  
 Contractor: Earl F. Wakefield  
 Comm: 5/19/52 Comp: 5/29/52

NE NE SW  
 19-13-21W  
 Trego County, Kansas  
 Casing: 105' of 8 5/8"

Elevation: 2246 D.F.

Shale & Lime	75
Lime	120
Shale, Shells & Sandstone	580
Red Bed	600
Sand & Shale	1005
Red Bed Sand	1250
Shale & Sand	1404
Shale & Shells	1680
Anhydrite	1695
Shale & Shells	2520
Shale & Lime	3465
Lime & Shale	3550
Lime	3735
Lime & Shale	3805
Shale & Lime	4000
Lime-Arbuckle	4050
Total Depth	4050

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct copy of the log on the Petty #1 well located NE NE SW 19-13-21W, Trego County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 5th day of June 1952.

C. Jeanne Gafrey



My Commission Expires: 12-23-54

RECEIVED  
 CONSERVATION COMMISSION  
 JUN 10 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 06-10-1952

INDEXED  
 FILED  
 JUN 19 1952  
 BOOK PAGE 19 LIST 51