


195
15-051-20278-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Trego County, Sec. 19 Twp. 13S Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines S/2 SW NW
Lease Owner Pickrell Drilling Company
Lease Name Herbert "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 10 19 74
Application for plugging filed May 10 19 74
Application for plugging approved May 10 19 74
Plugging commenced May 10 19 74
Plugging completed May 10 19 74
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	209.93'			

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1974
05-17-1974
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 800' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 215' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 10:45 P. M. May 10, 1974.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.
Kenneth J. Link (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link
Kenneth J. Link
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 11th day of May, 1974



Elaine H. Taylor
Notary Public.

DRILLERS LOG

#1 Herbert "A"

CASING RECORD: 203.93' of used 8-5/8" surface casing. COMPANY: Pickrell Drilling Company DESCRIPTION: S/2 SW NW Section 19-13S-21W Trego County, Kansas CONTRACTOR: Strata Drilling Company

TOTAL DEPTH: 4070' COMMENCED: May 1, 1974 COMPLETED: May 10, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock	0	70	Ran 203.93' of used 8-5/8" surface casing; set and cemented at 209.93' with 150 sacks of common cement, 2% gel and 3% C. C. Plug down at 10:45 P. M. May 1, 1974.
Shale & Shells	70	218	
Shale & Sand	218	1550	
Sand Streaks & Shale	1550	2036	
Lime & Shale	2036	3810	
Lime	3810	3825	
Lime & Shale	3825	3965	
Lime	3965	4070	

ROTARY TOTAL DEPTH: 4070'

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1974
05-17-1974
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Hole plugged as follows: Plugged at 800' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 215' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 10:45 P. M. May 10, 1974.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY
Kenneth J. Link
Kenneth J. Link

Subscribed and sworn to before me this 11th day of May, 1974.

My Commission Expires:
December 14, 1977

Elaine H. Taylor
Elaine H. Taylor, Notary Public

