

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-195-21,160-00-00

LEASE NAME DEUTSCHER

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER !

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 10 TWP. 13 RGE. 21W (E) or (W)

COUNTY ELLIS

Date Well Completed 4-21-83

Plugging Commenced 9-4-1992

Plugging Completed 9-4-1992

LEASE OPERATOR AL-LA-LYN OIL, INC.

ADDRESS 614 W 10th ST. ELLIS, KS. 67637

PHONE# (913) 726-3545 OPERATORS LICENSE NO. 7973

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-2-1992 (date)

by MARION SCHMIDT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? YES

Producing Formation TOR & marmaton Depth to Top 3472- Bottom 3819' T.D. 3824'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|-----------|-------|-----|--------|--------|-------------------------|
| | | | | 8 5/8" | 331' | -0- 180 sx circ |
| Marmaton | Oil & wtr | 3813- | 19' | 5 1/2" | 3905' | None dv1573 450 sx circ |
| Toronto | Oil & Wtr | 3472 | 74' | ----- | ----- | ----- |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to TD feet each set pumped 15 sx in annulus, 350# shut in. pumped 335 sx down 5 1/2" csg, 100 psi, shut in of 50#. used a total of 350 sx 65/35 w/8% gel. mixed 5 hulls after the first 15 sx down 5 1/2 csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing, Co.

License No. _____

Address P O Box 31 Russell, Ks. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AL-LA-LYN OIL, INC.

STATE OF KANSAS

COUNTY OF _____, ss.


ROBERT A. WAHLMEIER (Consultant)

(Employee of Operator) of _____

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert A. Wahlmeier

(Address) 2213 Virginia drive Hays, Ks. 67601



AND SWORN TO before me this 10th day of September, 19 92

NOTARY PUBLIC
 STATE OF KANSAS

MY APPT. EXPIRES 7-31-1994

My Commission Expires: July 31-1994

Notary Public