

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-20535-000

LEASE NAME Cox #2

WELL NUMBER _____

SPOT LOCATION NW SW NW

SEC. 10 TWP. 13s RGE. 21w (E) or (W)

COUNTY Trego

Date Well Completed _____

Plugging Commenced 9/18/84

Plugging Completed 9/28/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Southern States Oil Co.

ADDRESS P.O. Box 1365, Great Bend, Ks. 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3931'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	266'	none
				4 1/2"	3930'	1023'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from _____ feet to _____ feet each set.

Could not plug bottom. Could not get past 1028'. Shot pipe at 1023'. Pipe parted, pulled 26 joints of pipe. Plugged well with 60 cement, 15 gel, 80 cement with 5 hulls, 10 gel, 8 5/8 plug, & 50 sacks 50/50 poz 8% gel.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1984



My Commission expires: _____

Irene Hoover
Notary Public
STATE CORPORATION COMMISSION

OCT 04 1984
10-04-1984 Form CP-4
Revised 06-83

13-~~1951~~¹⁹⁷⁵-20535-00-00

DRILLERS LOG

No. 2 Cox

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 266' w/175 sx cement	CONTRACTOR:	Red Tiger Drilling Company	NW/4 SW/4 NW/4 Sec. 10-T13S-R21W Trego County, Kansas
4 1/2" @ 3,930' w/200 sx cement	COMMENCED:	January 16, 1979	
TOTAL DEPTH: 3,931'	COMPLETED:	February 6, 1979	ELEVATION: 2,200' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale, Sand & Shale	0	275	
Shale	275	778	
Shale & Red Bed	778	1100	
Sand	1100	1295	
Shale	1295	1385	
Shale & Red Bed	1385	1578	
Anhydrite	1578	1621	
Shale	1621	2055	
Shale w/Lime Streaks	2055	2315	
Shale & Lime	2315	2830	
Lime & Shale	2830	2980	
Lime	2980	3931	
RTD		3931	


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 13th day of February, 1979.

Joyce A. Hagermann
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1984
08-30-1984
CONSERVATION DIVISION
Wichita, Kansas