

15-195-20248-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Trego County, Sec. 19 Twp. 13S Rge. 21 (E) (W)XX
Location as "NE/CNW/SE/SW" or footage from lines NW SE SW
Lease Owner Pickrell Drilling Company
Lease Name Petty "C" Well No. 2
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 2 1973
Application for plugging filed October 2 1973
Application for plugging approved October 2 1973
Plugging commenced October 2 1973
Plugging completed October 2 1973
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production N/A 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4140 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	263	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 850' w/110 sx, Middle Plug @ 275' w/30 sx, Top Plug @ 40' w/10 sx.

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1973
CONSERVATION DIVISION
Wichita, Kansas
10-09-1973

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth Nat'l. Bank Bldg., Wichita, Ks. 67202
(Address)



Subscribed and sworn to before me this 3rd day of October, 1973.
Helen L. Sage
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth Nat'l. Bank Bldg.
 Wichita, Kansas 67202

LOCATION: Petty "C" No. 2, NW SE SW
 Sec. 19-13S-21W, Trego County, Kansas

Rotary Drilling Commenced 9-19-73

Rotary Drilling Completed 10-2-73

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: Run 7 Jts. of 8-5/8" surface pipe set at 263' K.B. Cemented with 150 sacks. Completed 6:30 P.M. Circulated.

No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>C. F. S.</u>
20	Top Soil	3730
50	Post Rock	3754
271	Clay & Shale	3765
560	Shale & Shells	3810
1210	Shale & Red Beds	3865
1450	Sand	
1734	Shale	
1774	Anhydrite	
1840	Shale & Lime & Shells	
2500	Shale & Lime	
3140	Lime & Shale	
3340	Shale & Lime	
3525	Lime & Shale	
3655	Lime	
3675	Lime & Shale	
3710	Lime	
3728	Lime & Shale	
3850	Lime	<u>Slope Tests</u>
3865	Lime & Shale	2500
3880	Lime	3000
4079	Lime & Shale	3500
4103	Arbuckle	4000
4140	Lime, RTD	


RECEIVED
 STATE CORPORATION COMMISSION
 OCT 9 1973
 10-09-1973
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By [Signature]
 C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 3rd day of October, 19 73, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.



My Commission Expires: April 17, 1977

[Signature]
 Helen L. Sage Notary Public