

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1965
03-01-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Don Knight of Knight Csg. Pulling Co., has this

date requested permission to plug the following described well:

Don Hellar Oil Co.,
Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Don Hellar Oil Company,

Complete Address: 1014 Union center, Wichita, Kansas.

Lease Name: Seibel Well No. 1

Location: W/2-SW-SW Sec. 5 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 3972 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

206' -- 8 5/8" Surface pipe, cement circulated.
3963' -- 5 1/2" Production casing cemented with 150 Sx.
Top of perforations @ 3338'.

Sand well back to 3300' and set 5 Sx. cement with dump bailer.

Pull 5 1/2", set plug @ 500' and fill to bottom of cellar with

Redi-Mix.

Very truly yours,

M. L. Nichols
Conservation Division Agent