

15-195-20100-00-00

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 28 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Tilco Et al.

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Egger Well No. 3

Location: NE-NW-NE Sec. 20 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 4025' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Delaney was instructed to plug the well as follows:

237'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 950' and displace 100 Sx.  
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent