



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Sullivan of Russ Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company.

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Glass Well No. 2

Location: SW-NE-NE Sec. 7 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 4000' Oil Well X

Gas Well Input Well SWD Well D. & A. Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

187'--8 5/8" Surface casing, cement circulated with 150 Sx.
3932'--4 1/2" Production casing cemented on bottom with 150 Sx. Top perforations @ 3755'.

Sand well back to 3725' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 135 Sx. cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent