



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission
CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 6 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date April 23, 1959, authorized the following plugging operation:

Operator's Full Name: O. C. Sutton

Complete Address: 407 - Ins. Bld. Wichita Kans.

Lease Name: Cross Well No. 1

Location: Se - Nw - Nw Sec. 23 Twp. 13 Rge. 21 (E) (W)

County: rego Total Depth: 3987

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: dry hole

Operator was instructed to plug well as follows:

Circulate hole with heavy mud set plug at 600' and displace
20 sac cement thru drill pipe, heavy mud to 200' set
plug and displace 15 sac cement, heavy mud to 40'
set cementing plug and use 1/2 sac dry hulls and 10 sac
cement, cementing to base of collar.

Very truly yours,

Signed: Hubert O. Larker
 Conservation Division Agent