

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS, 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1965

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this

date requested permission to plug the following described well:

Birmingham & Bartlett Drig. Co.

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Birmingham and Bartlett Drilling Co.,

Complete Address: 300 Kaufman Building, Wichita, Kansas.

Lease Name: Arnold Well No. A-2

Location: NW-NW-NW Sec. 23 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 3973 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

237' -- 8 5/8" Surface pipe, cement circulated.
3972' -- 5 1/2" Production casing cemented with 150 Sx. Top perforations from 3602' to 3608'.

Sand well back to 3590' and set 4 Sx. cement with dump bailer.
Pull 5 1/2" casing to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 240' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent