



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1973
11-26-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herb French of Pickrell Drilling Company has this

date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Petty Well No. C-3

Location: NW-NE-SW Sec. 19 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 4061 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. French was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 145 Sx.
Top of Dakota section @ 600'.

Circulate hole with heavy mud. Pull DP to 825' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent