



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION 10-05-1973 OCT 5 1973 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Herb French of Pickrell Drilling Company has this

date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Petty Well No. C-2

Location: NW-SE-SW Sec. 19 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 4140 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. French was instructed to plug the well as follows:

263'--8 5/8" Surface casing, cement circulated with 170 Sx. Top of Dakota section @ 625'

Circulate hole with heavy mud. Pull BP to 850' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Nichols

Conservation Division Agent