

State of Kansas



15-195-20278-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION MAY 13 1974 05-13-1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Charles Steincamp of Strata Drilling Incorporated has this date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 5th National Bank Bldg., Wichita, Kansas.

Lease Name: Herbert Well No. A-1

Location: S/2-SW-NW Sec. 19 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 4070' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx. Top of Dakota section @ 575'.

Circulate hole with heavy mud. Pull DP to 800' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

[Signature] Conservation Division Agent