



15-~~15~~¹⁹⁵-20209-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas
04-03-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Owens of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Owens guarantees payment of the plugging fee.

Operator's full Name: Tenneco Oil Company,

Complete Address: 200 Classen Center-East Bldg., Oklahoma City, Okla.

Lease Name: V. M. Nelson Well No. 1-16

Location: NE-NE-SE Sec. 16 Twp. 13 Rge. (E)(W) 21

County: Trego Total Depth 4005' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Owens was instructed to plug the well as follows:

208'--8 5/8" Surface casing cement circulated with 175 Sx.
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 200' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent