



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Terry Piesker of Frontier Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Frontier Oil Co

Complete Address: 1720 KSB&T Bldg Wichita, Kansas 67202

Lease Name: Cox Well No. 1

Location: SW-NW-NW Sec. 10 Twp. 13 Rge. 21 (E) (W)

County: Trego Total Depth: 3952'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: drilled approximately 2 yrs ago

Mr. Piesker was instructed to plug the well as follows:

8 5/8" set @ 280' w/180 sk cement circ.
Ordered 140 sk 50% pozmix 4% gel, 3% CA-cl, 18 s. gel
3 s. hulls, + 8 5/8" plug & pumped in w/pump truck 2 s. hulls ->
10 s. gel, -> 1 hull -> 70 s. cement -> 8 s. gel -> Rel Plug -> 70 s. cement.
Max PSI 750# 5:30 p

(Cmt by Allied)

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

JAM 27 1982
01-27-1982
CONSERVATION DIVISION
Wichita Kansas

Dennis L. Hamel
Conservation Division Agent