

15-051-04308-00-00

Form CP-3
Rev. 6-26-62

44
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 1 1963
02-01-1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Birmingham - Bartlett
Complete Address: 300 Kaufman Bldg Wichita, Kans
Lease Name Flax Well No. 4
Location SE SR SW Sec. 20 Twp. 13 Rge. (E) (W) 20
County Ellis Total Depth 3945
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Glenn & Smith
Address: Ellinwood, Kansas License No. 396
Operation Completed: Hour 12:15PM Day 29 Month 1 Year 63

The Above well was plugged as follows:

8 5/8" 208' circulated with cement - 5 1/2" 3928' with 175 sax cement - PB 3400'
Perf 3326'.

Sand back to 3310', set 4 sax cement with dump bailer - pulled 2910' 5 1/2" to
550', circulated hole with heavy mud through 5 1/2" (35 sax Gel), displaced 20
sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement
through 5 1/2" at 180', heavy mud to 35', set bridge and filled to bötton cellar
with cement.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Petty*
Well Plugging Supervisor

DATE 2/1/63
INV. NO. 6505-W