

15-051-20244-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
04-29-1968Operator's Full Name Murfin Drilling CompanyComplete Address: 617 Union Center Wichita, KansasLease Name Younger Well No. 1Location NW SW SE Sec. 20 Twp. 13 Rge. 20 (E) (W) XCounty Ellis Total Depth 3548Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Co, Tools

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 6:15 A Day 26 Month 4 Year 1968

The Above well was plugged as follows:

RTD 3548' 8 5/8 csg set at 226' cwc 165 sc. Cem. Mat. 100 sc 6% 50-50 poz cement.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.

thru drill-pipe. Heavy mud to 210'-set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/29/68INV. NO. 7662-WSigned: Leo J. Messer  
Well Plugging Supervisor