

15-051-20235-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

11-01-1968
RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company

Complete Address: Box 797 Great Bend, Kansas

Lease Name Rankin Well No. 2

Location SE NE SW Sec. 33 Twp. 13 Rge. 20 (E) (W) X

County Ellis Total Depth 3918'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12N Day 30 Month 10 Year 1968

The Above well was plugged as follows:

Total depth 3918' 8 5/8 csg set at 200' cwc

4 1/2 csg set at 3916' cw 100 sc

4 1/2 csg PBTB 3720' Top perf. 3577'

Set plug at 3500' poured 10' sand and dumped 4 sc cmt W/ dump bailer.

Shutoff and recov. 750' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sc gel W/4 sc hulls, 120 sc 50-50 poz cmt W/6% gel,

4 sc gel, 1 sc hulls, plug and 10 sc cement.

(0-40) Cmt. (40-200) Gel (200-700) Cmt. (700-TD) gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo J. Massey
Well Plugging Supervisor

INVOICED

DATE 11/4/68

INV. NO. 8954-11