

15-051-19087-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 7 1961  
15-07-19(0)  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: NE SW NW Sec. 33 Twp. 13 Rge. \_\_\_\_\_ (E) 20 (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3934

I have this date completed supervision of plugging of:

Lease Name: Rankin Well No. 1

Operator's Full Name: Sinclair Oil & Gas

Complete Address: Box 466 Chase, Kansas

Plugging Contractor Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A x

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No x

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5 PM Day 22 Month 5 Year 61

The above well was plugged as follows:

10 3/4" 250' circulated with cement - 5 1/2" 3932'  
Filled with sand to 3525' set 4 sack cement with dump bailer, pulled  
2400' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" at 600',  
50 sack Gel - displaced 20 sack cement through 5 1/2" at 600', heavy mud to  
180', displaced 20 sack cement through 5 1/2" at 180', heavy mud to 35'  
set bridge and 10 sack cement to bottom cellar.  
Mudding and cementing by Knight Co pump truck.

Signed: Edson Perry  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED  
DATE 6/28/61  
INV. NO. 3313-11