

15-195-30002-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1965

03-01-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don Hellar Oil Company,

Complete Address: 1014 Union Center, Wichita, Kansas.

Lease Name Seibel Well No. 1

Location W/2-SW-SW Sec. 5 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 3972

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas License No. 436

Operation Completed: Hour 6:00PM Day 25 Month 2 Year 1965

The Above well was plugged as follows:

206'--8 5/8" Surface pipe, cement circulated.

3963'--5 1/4" Production casing cemented with 150 Sx. Top perforations @ 3338'.

Sanded well back to 3300' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing, set plug @ 500' bridged hole and filled to bottom

of cellar with Redi-Mix. (used 6 yards Redi-Mix)

(Recovered approximately 3400' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/1/65

INV. NO. 742-W

Signed: W. L. Nichols
Well Plugging Supervisor