

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

API NO. 15-195-20998 - 00 00
 COUNTY Trego SEC. 5 TWP. 13S RGE. 21 E/W
 Location as in quarters or footage from lines:
 SE/4, NW/4, SE/4

Lease Owner Zenith Petroleum Corporation Kansas Partnership No. 1
 Lease Name Harold Deutscher Well No. 3
 Office Address One Northwind Plaza Suite 502, 7600 W. Tidwell, Houston, Tx.
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil 77040
 Date Well Completed June 23, 1982
 Application for plugging filed June 1, 1983
 Plugging commenced June 7, 1983
 Plugging completed June 7, 1983
 Reason for abandonment of well or producing formation Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
 Producing formation Arbuckle Depth to top 3974' bottom 4080' T.D. 4080'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	345'	None
				4-1/2"	4065'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Loaded hole with saltwater. Pumped in
sequence the following: 25 sx 50/50 pozmix containing 2% gel and
3% calcium chloride; 4 sx of cottonseed hulls and 12 sx of gel mixed
with water; rubber cementing plug; 115 sx of cement as above.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services, License No. 5287,
Colorado Derby Building, Suite 600, Wichita, Kansas 67202

STATE OF Texas COUNTY OF Harris, ss.


E. B. Rogers (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) E. B. Rogers
7600 West Tidwell, Houston, Tx.
 (Address) 77040

SUBSCRIBED AND SWORN TO before me this 23 day of June, 1983

Susan A. Hiseh
 Notary Public.

My Commission expires: 6-21-86



RECEIVED
 STATE CORPORATION COMMISSION

JUN 27 1983

Conservation Division
 Wichita, Kansas