

15-195-00090-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Trego County, Sec. 5 Twp. 13 Rge. 21W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SE

Lease Owner Hellar Drilling Company, Inc.

Lease Name Deutscher Well No. 1

Office Address 1014 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-29 1959

Application for plugging filed 8-29 1959

Application for plugging approved 8-29 1959

Plugging commenced 8-29 1959

Plugging completed 8-29 1959

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, orally

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3995 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	238	8-5/8"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 600' with 20 sacks cement.
Filled up with mud 230', set 2nd plug with
20 sacks cement. Filled up to 40' set 3rd
plug and cemented to bottom of cellar with
10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1959
09-03-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.

Address 1014 Union Center


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

D. L. Hellar (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar
1014 Union Center
(Address)

Subscribed and Sworn to before me this 2nd day of September, 19 59

My commission expires March 6, 1961.
Wanda Lou Bruce
Notary Public.



PLUGGING
FILE SEC 5 T. 13 R. 21W
BOOK PAGE 1 LINE 52

15-195-00090-00-00

RECEIVED
STATE OIL & GAS COMMISSION

SEP 3 1959

CONVEYANCE DIVISION
Wichita, Kansas

WELL LOG

OWNER:
CONTRACTOR:
LEASE:
LOCATION:

Hellar Drilling Company, Inc.
Hellar Drilling Company, Inc.
Deutscher #1
NW NW SE, Sec. 5-13-21W
Trego County, Kansas
August 20, 1959
August 29, 1959
8-5/8" set @ 238' w/150 sacks
cement

COMMENCED:
COMPLETED:
CASING:

0 - 217	Surface clay & post rock
217 - 650	Shale
650 - 1100	Red bed & shale
1100 - 1460	Sand & shale streaks
1460 - 1675	Shale & sand
1675 - 1720	Anhydrite
1720 - 2235	Shale
2235 - 2405	Shale & lime streaks
2405 - 2538	Lime & shale
2538 - 2652	Lime - Ft. Riley
2652 - 2852	Shale
2852 - 2987	Shale & lime
2987 - 3140	Lime & shale
3140 - 3445	Shale & lime
3445 - 3488	Topeka lime
3488 - 3918	Lime
3918 - 3952	Lime & chert
3952 - 3998	Chert & lime
3995	Rotary Total Depth
	D & A


STATE OF KANSAS) SS
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the DEUTSCHER #1, located NW NW SE, Section 5-13-21W, Trego County, Kansas, as reflected by the files of the HELLAR DRILLING COMPANY, INC.

HELLAR DRILLING COMPANY, INC.

BY D. L. Hellar
D. L. Hellar, President

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 2nd day of September, 1959.



Manda Lou Bruce
Notary Public

My commission expires March 6, 1961.

PLUGGING
FILE SEC 5 1/8 21W
BOOK PAGE 1 LINE 32