


15-051-01020-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec 31 Twp 13S Rge 20W (X) (W)
Location as "NE/CNW/SW" or footage from lines NW 1/4 NW 1/4 NE 1/4
Lease Owner Leben Drilling, Inc. and Nadel & Gussman
Lease Name Kroeger Well No. 1
Office Address 905 Central Bldg., Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-31-58 19
Application for plugging filed 10-31-58 19
Application for plugging approved 10-31-58 19
Plugging commenced 10-31-58 19
Plugging completed 10-31-58 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3980 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	235.54'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 600' w/20 sacks cement
2nd plug @ 220' w/15 sacks cement
top plug @ 40' w/10 sacks cement & 1/4sx. hulls.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November

June 17, 1961



RECEIVED
STATE CORPORATION COMMISSION
Ruth N. Benjamin Notary Public.

NOV 20 1958
11-20-1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 31 T 13 R 20W
BOOK PAGE 146 LINE 32

15-051-01020-00-00

DRILLER'S LOG

OPERATOR: LEBEN DRILLING, INC. AND NADEL & GUSSMAN
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: KROEGER #1
 LOCATION: NW 1/4 NW 1/4 NE 1/4 SEC. 31-13S-20W
 ELLIS COUNTY, KANSAS
 COMMENCED: 10-22-58
 COMPLETED: 10-31-58

0	30	Surface Clay		
30	60	Sand	LOG TOPS:	
60	234	Shale	Heebner	3526
234	1380	Shale, Shells & Sand	Toronto	3546
1380	1595	Shale & Shells	Lansing K.C.	3566
1595	1630	Anhydrite	Ds. K.C.	3815
1630	1830	Shale & Lime	Hermaton	3872
1830	2100	Shale & Shells	Conglomerate	3909
2100	2215	Shale w/Lime	Arbuckle	3926
2215	2345	Shale		
2345	2745	Shale & Lime	Elevation	2279 K.B.
2745	3445	Shale & Lime		
3445	3663	Lime		
3663	3980	Lime		
	3980	Rotary Total Depth - D & A		

Set 235.54' of 8 5/8" surface casing with 140 sacks cement & 2% CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Kroeger #1, located NW 1/4 NW 1/4 NE 1/4 of Section 31, Township 13 South, Range 20 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 20 1958
 CONSERVATION DIVISION
 Wichita, Kansas

LEBEN DRILLING, INC.

Frank Hamlin
 Frank Hamlin

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of November, 1958.

Ruth N. Benjamin
 Ruth N. Benjamin, Notary Public

My commission expires: June 17, 1961

PLUGGING
 FILE SEC. 31 T. 13 R. 20W
 BOOK PAGE 146 LINE 32