

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

AP I 15-051-23,551-00-00 COUNTY ELLIS SEC. 31 TWP. 12S RGE. 20W E/W
 Location as in quarters or footage from lines:
150' E of NW SE NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner W.L. KIRKMAN, INC.
 Lease Name KROEGER Well No. # 1
 Office Address P.O. BOX 18611, WICHITA, KS. 67207
 Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
 Date Well Completed 7:45 A.M. 7-30-83
 Application for plugging filed 8-5-83
 Plugging commenced 5:00 A.M. 7-30-83
 Plugging completed 7:45 A.M. 7-30-83
 Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GIB SCHECK
 Producing formation _____ Depth to top _____ bottom _____ T.D. _____
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record


Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	266'	J-55	6 Jts.	

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Well was plugged with 200 sks of 50/50 paus 4% gel, 3% cc. Plugs were staged
 at: 20 sks at 3900', 20 sks at 1550', 80 sks at 825', 40 sks at 300',
 20 sks at 40', 10 sks rat hole, 10 sks mouse hole.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Sun Cementing, Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
 _____ (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.



(Signature) Arnie Little ARNIE LITTLE
VICE-PRESIDENT
BOX 18611, WICHITA, KS. 67207
 (Address)

SUBSCRIBED AND SWORN TO before me this 5TH day of AUGUST, 19 83

Mary Kay Oeding
 MARY KAY OEDING Notary Public.

MY APPOINTMENT EXPIRES NOV. 28, 1984

RECEIVED
 STATE CORPORATION COMMISSION

AUG 09 1983
 08-09-1983
 CONSL. DIVISION
 Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

15-051-23551+00-00

W E L L L O G



WELL NAME: KROEGER #1

WELL LOCATION: 150' E of NW SE NW
SEC. 31-13S-20W

OPERATOR: W.L. KIRKMAN, INC.

COMMENCED: 4:30 P.M. 7-21-83

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 7:45 A.M. 7-30-83

CASING RECORD: 8 5/8" set @ 266'

FORMATION:

FROM:


TO:

Sand-Dirt	0	84
Gray Shale & Sand	84	270
Clay Sand	270	775
Gray Shale	775	1550
Red-Shale	1550	1594
Anhydrite	1594	1644
Shale	1644	1683
Shale & Clay	1683	2058
Lime & Shale	2058	3961

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
150' E of NW SE NW, SEC. 31-13S-20W, Ellis Co., Kansas TO THE BEST OF MY

KNOWLEDGE



RECEIVED
STATE CORPORATION COMMISSION
08-09-1983
AUG 09 1983

ALDEBARAN DRILLING CO., INC.
ARNIE LITTLE
VICE-PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 5TH DAY OF AUGUST, 1983

MY APPOINTMENT EXPIRES NOV. 28, 1984
MY APPOINTMENT EXPIRES: _____

Mary Kay Oeding
MARY KAY OEDING NOTARY PUBLIC