

LEASE NAME Boos

WELL NUMBER #1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 31 TWP. 13 RGE. 20 (E) or (W)

COUNTY Ellis

Date Well Completed 4/1970

Plugging Commenced 11/3/99

Plugging Completed 11/3/99

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

JAN 03 2000
 01-03-2000
 CONSERVATION DIVISION

LEASE OPERATOR Wichita, Kansas Charter Energy, Inc.

ADDRESS P O Box 252, Great Bend, KS 67530

PHONE (316) 793-9090 OPERATORS LICENSE NO. 9090

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/1/99 - verbal (date)
Herb Deines (KCC District Agent's Name).

ACO-1 filed? if not, is well log attached? --

Producing Formation LKC Depth to Top 3544 Bottom 3790 T.D. 3934

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	250	None
				5 1/2"	3933	None
				2"		1030
Tubing parted						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from feet to feet each set:
Ran tubing to 1000'. Mixed and pumped 100 SX 60/40 pas - 10% gel with 50#
Closeal and 5 sx hulls. Pulled tubing to 600'. Mixed and pumped 50 sx as above
with 3 sx hulls. Pulled tubing & pumped 50 sx with 7 sx hulls. Topped off with
35 sx. Hole full. Took to 8 5/8". Mixed & pumped 75 sx with 1 sx hulls.
 Max. PSI 300#. SI @ 100#.

Name of Plugging Contractor Allied Cementing License No.

Address Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Already billed per KCC #2000060901

STATE OF Kansas COUNTY OF Barton, ss.

Steve Baize (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 252, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 30th day of December, 1999

[Signature]
 Notary Public

My Commission Expires: 2/17/2001



(R)