

3-10-88

133

R

6 070651

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21813-00-00
180' S of
SE NE SE, SEC. 5, T 13 S, R 21 (W/A)
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Operator: Dreiling L.T.D. of Colorado
Name & Address: 410 17th St. #1140
Denver, Colorado 80202

Lease Name Deutscher Well # B-1
County Trego 130.42
Well Total Depth 4013 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Box 31, Russell, Kansas 67665

Company to plug at: Hour: 1:00PM Day: 10 Month: Mar Year: 1988

Plugging proposal received from Dave Dreiling and Gary Geist

(company name) Dreiling L.T.D. and Midwestern Pipe Works (phone) 913-625-4670

were: 8 5/8" - 253' S.P. cwc w/N.A. 5 1/2" csg set at 4010' w/N.A. Perfs 3560' to 3986'; Sanded off bottom to 3491' and w/5 sks cement. Shot at 2500'. Recovered 2500' of 5 1/2" csg; Proposal 200 sks of A.T.L. 65/35 Pozmix 10% Gel and 5 sks Hulls. Pump in 8 5/8" csg with pump truck. Shut in under pressure.

Plugging Proposal Received by MJS (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 PM Day: 10 Month: Mar Year: 1988

ACTUAL PLUGGING REPORT Ordered 200 sks 65/35 Poz 10% Gel and 5 sks of Hulls.

Pumped in with pump truck. Pumped in 8 5/8" S.P. 25 sks cement, followed with 175 sks cement w/5 sks Hulls added in. Max pressure 500 Psig.; shut in at 2500' Psig. Cemented by Allied Cement.

RECEIVED

APR 22 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOLCED

DATE 4-26-88

INV. NO. 20460

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt