

1-12-88

15-195-20998-00-01

To: **6 070624**
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15 195-20-9882-00-01
 SE NW SE, SEC. 5, T 13 S, R 21 W/8
 _____ feet from S section line
 _____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804Lease Name Duetscher Well # 3-AOperator: Dreiling L.T.D.County Trego 132.60Name & Address 410 17th Street #1140Well Total Depth 4080 feetDenver, Colorado 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 345Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing Co. License Number _____Address East Hwy 40 Hays, Kansas 67601Company to plug at: Hour: 10:00AM Day: 12 Month: Jan Year: 19 88Plugging proposal received from Dave Dreiling(company name) Dreiling L.T. D. of Colorado (phone) _____were: 8 5/8" 345' S.P. cwc w/175 sks cmt. 4 1/2" csg set at 4065' w/250 sks cmt.5 1/2" csg. Perf at 1300' cwc w/405 sks cmt. No csg recovery. Perfs at 3740' - 3328'

Plug back at 4065'. Proposal 200 sks 65/35 Poz 10% Gel and 5 sks Hulls. Load and pres-
sure annulus with cmt. In 4 1/2" csg load and pressure with cmt.

Plugging Proposal Received by Marion J. Schmidt
 (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____Operations Completed: Hour: 11:00 AM Day: 12 Month: Jan Year: 19 88ACTUAL PLUGGING REPORT Ordered 200 sks Econolite, 65/35 Poz 10% Gel and 5 sks Hulls.Pumped in with pump truck. Pumped in 6 sks cmt in annulus. Max Psig. 400'.Shut in at 400 Psig. Pumped in 4 1/2" csg 175 sks cmt and Hulls. Max pressure 800 Psi.Shut in at 800 Psig. Cemented by Halliburton Cement.

Remarks: _____
 (If additional description is necessary, use BACK of this form.)

INVOICED
 I did not observe this plugging.

DATE 1-26-88INV. NO. 19658Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt

FORM CP-2/3 LR
 Rev. 01-84