

15-195-20, 998-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15

SE, Sec. 5, T 13 S, R 21 W
1650 1570 S TD KCC
feet from S section line
1650 1960 E JD-KCC
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6249

Lease Name Deutscher Well # 3

Operator: Zenith Petroleum Corp.
Name & Address P.O. Drawer N. Great Bend, Mo.
67530

County Trego

Well Total Depth 4080 feet \$132.60

Conductor Pipe: Size 5" feet

Surface Casing: Size 8 5/8" feet 352

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number 5287

Address E. 8th. St. Hays, Mo. 67601

Company to plug at: Hour: 10:00 AM Day: 7 Month: 6 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Dan Mearally

(company name) Zenith Petroleum Corp. (phone) 913-625-3431

were: Order 140 lbs 50 pos mix - 4% Red. - 3% Gel. Cel.,
4 lbs. hulls & 4 1/2" plug. Pumped in 4 1/2" casing.

Signed *Arthur G. Rebel*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 AM Day: 7 Month: 6 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 352' SP. case w/ 175 lbs. 4 1/2" set at 4043'

Top perf. at 3328'. Staged from 1300' to surface w/ 500 lbs.
Pumped in 4 1/2" casing, 25 lbs. cement, 4 lbs. hulls, 8 lbs. Gel.,
released plug & followed w/ 115 lbs. cement w/ 600 pounds pres.
8 5/8" cemented to surface.

Remarks: Cemented By Halliburton

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

Signed *Arthur G. Rebel* ✓
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 6-20-83
INV. NO. 4637-W

JUN 13 1983
CONSERVATION DIVISION
Wichita, Kansas