

4-110073

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-20,587-00-00

SE SE SE /4 SEC. 31, 13 S, 20 W
330 feet from S section line
330 feet from E section line

Operator license# 9090

Lease: Boos Well # 1

Operator: Charter Energy, Inc.

County: Ellis 127.86

Address: P.O. Box 252
Great Bend, Kansas 67530

Well total depth 3934 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Doe's Well Service License# 32030

Address: P.O. Box 353 - West Wichita Avenue - Russell, Kansas 67665

Company to plug at: Hour: 1:00 P.M. Day: 2 Month: November Year: 1999

Plugging proposal received from: Steve Baize

Company: Charter Energy, Inc. Phone: 316-793-9090

Were: Ordered 350 sxs 60/40 pozmix 10% gel and 700# hulls.
Plug with tubing.
Fish at 1016' - could not get any further. Operator asked to emergency plug.

Plugging Proposal Received by: Roger Moses
Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:15 P.M., Day: 3, Month: November, Year: 1999

Actual plugging report: 8 5/8" set at 250' w/150 sxs cmt. 5 1/2" casing at 3933' w/150 sxs.
Ran tubing to top of fish - pumped 100 sxs cement and 500# hulls and 50# celloflake. Pulled tubing to 400' and pumped 50 sxs cement with 300# hulls. Pulled all tubing and circulated with 50 sxs cement and 700# hulls. Tied to 8 5/8" S.P. - pumped 75 sxs cement with 100# hulls to Max. P.S.I. 300#. S.I.P. 100#. Tied back to 5 1/2" casing and pumped 35 sxs cement and shut in.

Total 310 sxs 60/40 pozmix and 1500# hulls with 50# celloflake.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2256 GL

I did / did not observe the plugging.

Roger D. Moses
(AGENT) ED

STATE CORPORATION COMMISSION

INVOICED

DATE 12/3

INV. NO. 120901

NOV 19 1999
11-19-1999
CONSERVATION DIVISION
Wichita, Kansas

(R)

LEBEN DRILLING, INC. #1 BOOS 31-13-20W
 WICHITA, KANSAS SE SE SE
 Contr. LEBEN DRILLING, INC.; Cty. ELLIS
 Geol. GEO. WAITE Pool GOITTSCHALK BROS. CONF
 E. 2261 KB Cm. 2/25/70 Cp. 4/9/70 IPP 20 BOPD + 4 BWPD
 API 15-051-20,587 MARM 3870-84

LOGTops	GG	Depth	Datum
*ANHY		1578	+ 683
*B ANHY		1626	+ 635
HEEB		3503	-1242
TOR		3523	-1262
LANS		3544	-1283
BKC		3790	-1529
MARM		3855	-1594
ARB		3904	-1643
LTD		3934	-1673
RTD		3934	-1673
*DRILLERS TOPS			

Csg. 8 5/8" 250/150sx; 5 1/2" 3933/150sx
 DST(1) 3538-73/1', 2205'GIP, 146'MO, 600'FREE OIL (GR 39), BHP 992-970#, FP 52-298#
 DST(2) 3580-3610/1', 2400'GIP, 60'HO & GCM, 120'FRGY OIL, 120'FRGY OIL W/TR W, 120'OCW, BHP 758-709#, FP 37-224#
 DST(3) 3621-38/1', 60'GIP, 360'OCW, 588'WTR, BHP 888-880#, FP 37-488#
 DST(4) 3728-38/60", GTS/55" TSTM, 1765'CLEAN OIL, 190'FRGY OIL, 190'MO, (GR 29), BHP 558-558#, FP 37-724#
 DST(5) 3868-90/1', 250'GIP, 126'FREE OIL, 190' MO, 60'FRGY OIL, (GR 33), BHP 1136-1083#, FP 45-186#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)

LEBEN DRILLING, INC. #1 BOOS 31-13-20W
 SE SE SE

DST(6) 3603-23(sp)/1', 750'GIP, 180'HO & GCM, BHP 746-656#/30", FP 22-90#

PF 3870-72 & 3882-84 (MRM) FU 250'OIL/12HRS, SWB 180PH, N/W, N/T A
 2000 SWB PT LD & SWB 2.6 BOPH, N/W FU 1250'OIL & 50'WTR/12HRS, TSTG
 P 80 BO N/W; P 32 BO PLUS 4 BW