

4-18-88

6 070668

API NUMBER 15-195-21548-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NW, SEC. 20, T 13 S, R 21 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 7875

Operator: Strata Energy Res.
Name & Address: 4010 Birch St. #130

Newport Beach, Ca. 92660

feet from S section line
feet from E section line

Lease Name Denning Well # 2
County Trego 130.85

Well Total Depth 4026 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Box 31 Russell, Ks. 67665

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Robert Wahlmeier

(company name) Strata Energy Res. (phone) 714-261-8181

were: 8 5/8" - 265' SP cir w/ NA. 4 1/2" casing set @ 4025' w/160 sx.cmt. Staged- F.O. Tool

@ 1676' cir w/ 200 sx cmt. Perfs 3924-48'. No pipe recovery. Proposal 200 sx 65/35 pozmix,

10% gel, 2% additive and 5 sx hulls, -ump in with pump truck, load and squeeze with cement

both the 4 1/2" casing and annular space between 4 1/2" casing and SP with cement.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00PM Day: 18 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Ordered 200 sx 65/35 pozmix, 10% gel, 2% additive and 5 sx hulls.

Pumped in with pump truck. Pumped in annulus 10 sx cmt. Max pressure 300 psi. Shut in

300 psi. Pumped in 4 1/2" casing 25 sx cmt followed with 140 sx cmt w/ 5 sx hulls added in.

Maximum pressure 800 psi. Shut in @ 300 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Cemented by Allied Cementing. 07-06-88 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-8-88

INV. NO. 21247

CONSERVATION DIVISION Wichita, Kansas Signed Marion J. Schmidt (TECHNICIAN)