

4-18-88

6 070666

API NUMBER 15-195-21581-60-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NE NW, SEC. 20, T 13 S, R 21 W 10

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7875

Lease Name Denning Well # #3

Operator: Strata Energy Resources  
Name & Address 4010 Birch Street #130  
Newport Beach, California  
92660

County Trego 130.81

Well Total Depth 4025 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 258

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated Allied Cementing Co.

Plugging Contractor Allied Cementing Co. License Number \_\_\_\_\_

Address Box 31, Russell, Kansas 67665

Company to plug at: Hour: 10:00 am Day: 18 Month: April Year: 1988

Plugging proposal received from Robert Wahlméier

(company name) Strata Energy Resources (phone) 714-261-8181

were: 8 5/8" - 258' sp cir w/na. 4 1/2" casing set @ 4024' w/ 160 sx cement. Perfs @ 3919-3940'. PBTB 3966, no pipe recovery. Proposal perforate 4 1/2" casing @ 835' and 1660'. Order 250 sx 2% additive, 65/35 pozmix, 10% gel, and 5 sx hulls. Pump in with pump truck. Load both 4 1/2" casing and annular space between 4 1/2" casing and 8 5/8" with cement. Shut in under pressure.

Plugging Proposal Received by Marion Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 18 Month: 4 Year: 1988

ACTUAL PLUGGING REPORT Ordered 250 sx 65/35 pozmix, 10% gel, and 5 sx hulls. Pumped in 8 5/8" and 4 1/2" casing with pump truck. Perf 4 1/2" casing @ 835' and 1660'. Pumped in 4 1/2" casing with annulus open 25 sx cmt; followed with another 175 sx cmt w/5 sx hulls added in, cement circulated out of annulus after 170 sx cmt. Max. pressure 600 psi. Shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1988

Remarks: By Allied Cmt.  
(If additional description is necessary, use BACK of form)

INVOICED  
Do not attempt to observe this plugging.

DATE 7-8-88

INV. NO. 21248

Signed Marion Schmidt  
(TECHNICIAN)  
Marion Schmidt