

To: **6 070786**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-25
API NUMBER 15-195-01553-00-00

NE NE NE, SEC. 7, T 13 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

_____ feet from S section line

_____ feet from E section line

Operator: Dreiling Oil Inc.

Lease Name Glass Well # 1

Name & Address Box 1000

County Trego 129.22

Well Total Depth 3976 feet

Victoria, Ks. 67671

Conductor Pipe: Size 0 feet

Bill Draper

Surface Casing: Size 8 5/8 feet 185

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Box 31, Russell, Ks. 67665

Company to plug at: Hour: AM Day: 25 Month: July Year: 19 89

Plugging proposal received from Ivan Edsall

(company name) Dreiling Oil Inc. (phone) _____

were: 8 5/8" 185 s.p. cwc w/150 sks cement. 5 1/2" casing set at 3959' w/150 sks

cement. D.V. tool at 1675' cwc w/434 sks cement. Perfs 3498' to 3741'. No pipe recovery

Proposal 250 sks 65/35 poz 8% gel and 5 sks hulls. Pump in with pump truck. Load

both 5 1/2" casing and 5 1/2" casing and 8 5/8" annulus with cement and shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 25th Month: July Year: 1989

ACTUAL PLUGGING REPORT Dreiling Oil ordered 250 sks 65/35 poz

8% gel and 5 sks hulls. Pumped in with pump truck.

1. Pressured annulus to 400 psig. Shut in at 400 psig. No cement.

2. Pumped in 5 1/2" casing w/250 sks cement w/5 sks hulls added. Max pressure 250 psig
shut in at 200 psig. Cemented by Allied Cementing, Russell, Ks.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED
(old / ~~sketch~~) observe this plugging.

DATE 8-3-89

INV. NO. 25531

Signed Marion J. Schmidt
(TECHNICIAN)

Marion J. Schmidt

Dennis Hamel
Dennis Hamel

FORM CP-2/3
Rev. 01-84