

To: **6 070806**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-14
API NUMBER 15- 195-21,157 -00-00
330 FENW NE
1090 FEL, SEC. 23, T 13 S, R 21 W7E
4950 feet from S section line
1090 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3456
Operator: A. F. G. Energy Inc.
Name & Address: Box 605
Russell, Ks. 67665
Terry Piesker

Lease Name Kuhn Trust Well # 3
County Trego 132.80
Well Total Depth 4086 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number
Address Russell, Ks. 67665

Company to plug at: Hour: AM Day: 14 Month: Nov Year: 19 89

Plugging proposal received from Terry Piesker

(company name) A.F.G. Energy (phone)

were: 8 5/8" 342' s.p. cwc w/190 sks cement. 4 1/2" casing set at 4086' w/275 sks cement.

Casing good. Ely. 2168' Ahhy 1515'. 5 1/2" casing. D.V. tool at 1579' cwc w/550 sks cement.

Proposal 250 sks 65/35 poz 8% gel and 5 sks hulls. Pump in with pump truck. Load both 4 1/2" casing and 4 1/2" casing and 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by *MJS* Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15PM Day: 14 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT A.F.G. ordered 250 sks 65/35 poz 8% gel and 5

sks hulls. (4 1/2" casing was D.V. at 1579' cwc w/550 sks cement). Pumped in with pump truck.

1. Pumped in 4 1/2" and 8 5/8" annulus w/14 sks cement. Max pressure 400 psig. Shut in at 400 psig. 2. Pumped 210 sks cement w/5 sks hulls added in 4 1/2" casing. Max pressure 1000 psig. Shut in at 500 psig.

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1989
12-01-89

Remarks: Cemented by Allied Cementing Russell, Ks.
(if additional description is necessary, use BACK of this form)

I (did / did not) observe this plugging.

INVOICED

Signed *Marion J. Schmidt*
(TECHNICIAN)

Marion J. Schmidt
FORM CP-2/3
Rev. 01-84

DATE 12-7-89

INV. NO. 26657