

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6 070807

8 11-1f
API NUMBER 15- 195-20,976-00-00

C NW NE, SEC. 23, T 13 S, R 21 W/E
4260 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Kuhn Trust Well # 2

Operator: A.F.G. Energy Inc.
Name & Address: Box 605

County Trego 128.18

Russell, Ks. 67665

Well Total Depth 3944 feet

Terry Piesker

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Russell, Ks. 67665

Company to plug at: Hour: AM Day: 14 Month: Nov Year: 19 89

Plugging proposal received from Terry Piesker

(company name) A.F.G. Energy Inc. (phone)

were: 8 5/8" 297' s.p. cwc w/175 sks cement. 4 1/2" casing set at 3943' w/200 sks cement.

Casing good. F.O. tool at 1560' cwc w/550 sks cement. Pump in with pump truck. Proposal 325 sks 65/35 poz 8% gel and 5 sks hulls. Load both 4 1/2" casing and 4 1/2" casing and 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received *MJS* Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15PM Day: 14 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT A.F.G. ordered 325 sks 65/35 poz 8% gel and

5 sks hulls. (4 1/2" casing F.O. tool). Pump in with pump truck. 1. Pumped 120 sks cement w/1 sk hulls. Max pressure 300 psig. Shut in 200 psig. 2. 4 1/2" casing pumped in 188 sks cement w/4 sks hulls. Max pressure 800 psig. Shut in at 500 psig.

Cemented by Allied Cement. Russell, Ks.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)
11-1-1 1089
12-01-89
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I did not observe this plugging.

Signed *Marion J. Schmidt*
(TECHNICIAN)

Marion J. Schmidt

DATE 12-7-89
INV. NO. 26656