

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21049-00-00
Spot: CSWNWNE Sec/Twnshp/Rge: 28-13S-21W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SAUER Well Number: 1
County: TREGO Total Vertical Depth: 4080 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 218
Production: Size 5.5 feet: 4077
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/05/2002 9:00 AM

Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC

Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 350 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/05/2002 11:15 AM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 218' w/150 sxs cement. 5 1/2" casing at 4077' w/175 sxs cement.
Perforated at 650' - 1675' - 2275'.
Ran tubing to 2300' - pumped 100 sxs cement and 300# hulls.
Pulled tubing to 1150' - pumped 100 sxs cement and 200# hulls.
Pulled tubing to 575' and circulated with 50 sxs.
Pulled all tubing and squeezed 5 1/2" casing with 100 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Tied to 8 5/8" x 5 1/2" annulus and instant pressure to 500#. No cement.
Total of 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED

JUN 21 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. HOXIE TANK - WATER.

Plugged through: TBG

District: 04

Signed

Roger Moses

(TECHNICIAN)

JOHN B. COLLINS
 1007 CODY, #A #1 SAUER 28-13-21W
 HAYS, KS 67601 SW NW NE
 CONTR DREILING OIL, INC. CTY TREGO

GEOL _____ FIELD RIGA SOUTH EXT (1/8 E)

E 2283 KB CM 7/9/82 CARD ISSUED 8/10/82 IP P 60 BOPD & WTR
 2278 GL LANS 3659-3710 OA
 API 15-195-21,049

| | |
|---|---|
| + | + |
| + | + |

| SMP | Tops | Depth/Datum |
|-----------|------------|-------------|
| ANH | 1664+ | 619 |
| B ANH | 1711+ | 572 |
| TOP | 3356- | 1073 |
| HEEB | 3586- | 1303 |
| TOR | 3606- | 1323 |
| LANS | 3622- | 1339 |
| BKC | 3872- | 1589 |
| MARM | 3957- | 1674 |
| PENN CONG | 4004- | 1721 |
| ARB | 4056- | 1773 |
| RTD | 4080- | 1797 |

8 5/8 " 218/150SX, 5 1/2 " 4077/175SX
 DST (1) 3646-3710 (LANS) / TIMES NA, REC 1890' OIL (GR 30').
 ALL PRESSURES NA
 MICT - CO. PF (LANS) 3659-82, 1 / 3699, 1 / 3720, 1 / 3710, AC
 9000G, SWB LD, TSTD, POP, P 60 BOPD & WTR (AMT NA) 8/15/
 82

INDEPENDENT OIL & GAS SERVICE