

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-195-21,127-00-00

SE, Sec. 19, T 13 S, R 21 W R  
330 feet from NO section line

990 feet from NO section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6127

Lease Name FLAX-T NORTH Well # 1-8

Operator: TAURUS OIL CO.  
Name & Address PO. BOX 981  
HAYS, KANS.  
67601

County TREBO.

Well Total Depth 4127 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor RANGER DRUG. CO. License Number 6324

Address P.O. BOX 981 HAYS, KANS. 67601

Company to plug at: Hour: 2:00 PM Day: 13 Month: JAN Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO ERNIE WERTH

(company name) RANGER DRUG. CO (phone) 913-628-1727

were: 8 5/8" - 209 FT 50 CUC w/150 ST COMMON - 2% GEL - 3% CA-CL (ALLIED)  
ORDER 180 ST 50 Formix 6% GEL - 3% CA-CL. AND 8 5/8" PUC.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st plug @ 1740 FT w/20 ST CMT. -> 2nd plug @ 960 FT w/100 ST CMT. &

3rd plug @ 240 FT w/40 ST CMT. -> 4th plug <sup>50 FT IN BRIDGE</sup> HAYS - plug @ 40 FT w/10 CMT.

10 ST IN THAT HOLE (CIRCULATE)

Signed [Signature]  
(TECHNICIAN) DSIC

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 7:30 PM Day: 13 Month: JAN Year: 1983

ACTUAL PLUGGING REPORT PLUGGED AS STATED ABOVE.

RID NO PENETRATE ARBUCKLE (CEMENTED BY ALLIED CMT)

[Redacted]

Remarks: \_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

INVOICED

DATE 3-15-83 JAN 31 1983  
INV. NO. 3574-W CONSERVATION DIVISION  
Wichita, Kansas

Signed [Signature]  
(TECHNICIAN) DSIC