

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-195-21, 335-00-00

C 1/2 - NE-SE, Sec. 10, T 13 S, R 21 W E

1980 feet from N(S) section line

330 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7830

Lease Name MECCA-KUEHL Well # 1

Operator: MECCA PETROLEUM CORP.  
Name & Address 140 E. 19th AVE. #500  
DENVER, COLORADO.  
80203

County TREGO

Well Total Depth 3920 feet 128.37

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ALLEN DRILLING Co License Number TAG # 154

Address P.O. BOX 1389 GREAT BEND, MO, 67530

Company to plug at: Hour: 8:00 AM Day: 15th Month: JAN Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO GREG DAVIDSON

(company name) ALLEN DRILLING Co (phone) 316-793-5681

were:

8 5/8" - 299 FT SP. CUL #190 3/40 PERMIX GEL - CABL., 3% - 2% BY ALLIED BMT.  
ORDEX 200 50/50 PERMIX 6% GEL - 3% CA-CL - 2 3/4" FLAME AND 8 5/8" PLUG  
NO SHOW OR BLOW - NO CIRCULATION PROBLEMS, ELV. 2167 - ANH. 1530'  
ARBUCKLE @ 3900 FT

Signed Marion Schmidt  
(TECHNICIAN) 801C

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:00 AM Day: 15th Month: JAN Year: 1984

ACTUAL PLUGGING REPORT

ORDERED - 200 50/50 PERMIX 6% GEL - 3% CA-CL - 1 3/4" FLAME AND 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN PLUGS  
1st PLUG @ 3900 FT #20 3/4" CNT. -> 2nd PLUG @ 1540 FT #20 3/4" CNT.  
3rd PLUG @ 780 FT #100 3/4" CNT. -> 4th PLUG @ 240 FT #40 3/4" CNT.  
5th PLUG SOLID BRIDGE HULL'S - PLUG @ 40 FT #10 3/4" CNT., 10 3/4" RAT HOLE (CIRCULATE)

Remarks: \_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Marion Schmidt  
(TECHNICIAN) 801C

INVOICED RECEIVED  
STATE CORPORATION COMMISSION  
DATE 1-26-84 01-23-1984  
INV. NO. 9267-6  
1-15  
CONSERVATION DIVISION  
Wichita, Kansas